



# Status of the RPC production



S. Patricelli  
University of Naples and INFN





# Outline

- **Reminder of the project**
- **Quality assurance of detectors**
- **Integration**
- **Status of production and Q.C. improvements**
- **Conclusions**




# Participating institutes

- INFN Lecce (RPC production)
- INFN Naples (RPC production)
- INFN Roma 2 (RPC production)
- IHEP Protvino (RPC production)
- INFN Roma 1 (Trigger electronics)



# Barrel muon trigger schematic



-1 Schematic view of the trigger principle.

- Each station has 2 independent detector layers: 2 measurements in  $\eta$  and 2 in  $\phi$
- Low  $p_T$  trigger uses RPC1 and RPC2 stations
- High  $p_T$  trigger uses low  $p_T$  results and RPC3 station
- The two layers in each station have independent LV & HV power supplies



# What does an RPC look like?



Basic Unit

To cover 3.500 m<sup>2</sup>:

1004 Standard Units

16 different dimensions  
97% coverage

132 Special Units  
(with holes for alignment bars)

4 different dimensions  
3% coverage







# One Unit is a sandwich

**Gas volumes**

**Cu readout electrode panels**





**Paper honeycomb and Al support panels (Faraday cage)**

**Al lateral profiles**



# Front-End electronic is inside

Front-End boards with 8ch GaAs  
3 stage amplifier and discriminator



Back-End boards with terminating  
resistors and test pulse distribution



## A few numbers

Units:	1.136
Bakelite plates:	7.360
Gas volumes:	3.680
Electrode readout panels:	8.560
F.E. and B.E. Boards:	48.148
• Readout channels:	385.184






# Production principles

- All parts are produced by industry.
- To avoid duplication of tools and have higher efficiency in production, all additional works on detector parts are done in only one site.





# Production flow chart





## Quality control (1)

- All services (High Voltage, Low Voltage, Test, Gas connectors and Faraday cage) are mounted in Lecce.




- 2/3 of the Units are transported (group of 4 Units) in Rome 2 and Naples for quality control with cosmic rays. The remaining 1/3 is certified in Lecce.



## Quality control (2)

**Three test stations are operational**

**Tracking of CR is done with RPCs or Drift Chambers**



**Lecce**

**Roma2**




**Naples**

**Each station allows the simultaneous test of 8 Units**



## RPC - MDT integration (1)



**RPC Units (4 for low  $p_t$  stations and 2 for high  $p_t$  stations) are mounted and cabled on MDTs before installation in the ATLAS cavern.**


**A fast functionality test of the full packages is foreseen at this stage**







## RPC - MDT integration (2)



Trigger and read-out electronic (splitter and pad boxes) is mounted on top of the RPCs.

In some cases also MDT electronics has to be mounted on RPCs.

**Warning:** Trigger electronic schedule should be matched with muon barrel chambers installation schedule.



## RPC - MDT integration (3)

- MDT-RPC common supports are defined for BML and BMS chambers.
- For BOS chambers the project is under way.
- For BOL chambers the project not yet started.
- Space at CERN for system integration is still a problem to solve



# Preproduction

- A set of three BMS Units was assembled last year as a first test of assembly.
- Front-End and Back-End boards for these Units were not the final ones.
- Main goals of this preproduction were:
  - define all tools necessary for the assembly phase.
  - finalize services for the Units.



# Start of production

- Due to delay of tender procedures for Front-End boards production (**inside the detectors!**) the decision was taken to start production with a special order for 1.500 boards.
- The delivery of these boards had 2 months delay.
- These boards have now allowed the production of 24 Units, 16 for BOS and 8 for BOL chambers (largest size). Their assembly is being completed this week. 1 Unit in Lecce, 2 Units in Naples and 2 Units in Rome are under test with cosmic rays.



# Start of production


- All assembly tools and procedures for assembly of Units are now done or understood.
- Production database (MS Access) is operational.
- Unit assembly rate: **3 Units/day**. Not a bottleneck.
- A new assembly hall (no delay in production) is being prepared in Lecce.





# Mass production (1)

- In the schedule approved by EB Units production must be completed by the end of 2003.





## Mass production (2)

- Bakelite plates: on schedule
  - Electrode readout panels: on schedule
  - GaAs Front-End chips: produced (50.000)
  - Support panels: on schedule
  - Al profiles: produced and machined
  - Gas volumes: 2-3 months delay (improved Q.C.)
  - Front-End Boards: 4-5 months delay (tender procedures and industry)
- Of course, last point determines the global delay for Units assembly



## Improvements in Q.C. (1)

- Many discussions with LHCC referees have been about the coating of inner surfaces of gas volumes with linseed oil.
- For L3 and BaBar chambers (**streamer regime**) the coating procedure did not allow complete polymerization of the oil on the inner surface.
- Preliminary results of laboratory test of L3 chambers in Naples show negligible decrease of efficiency after 7 years of running. Efficiency loss in BaBar chambers mainly due to temperature increase.



## Improvements in Q.C. (2)

- Coating of ATLAS RPCs is done with a new “protocol” which assures complete polymerization of the inner surface. This procedure was already active at the time of the PRR in Feb. 1999.
- Bakelite surface is smoother and oil coating is thinner than that used for BaBar and L3.
- To avoid possible problems with dust deposition on the surface we will improve Q.C. during production.



## Improvements in Q.C. (3)

- Improve the oil/air filtering system.
- Visual inspection of samples after coating and periodical chemical analysis of linseed oil.
- Up to now gas inlets and outlets have been drilled, using all possible precautions to avoid dust deposition inside the gas volume.
- We are now producing injection molded pieces with holes to avoid drilling of the holes.





# Conclusions

- Production procedures are understood.
- Q.C. during gas volume production is being improved.
- Mass production has started but front-end PC boards have 4-5 months delay which will influence Units assembly.
- Schedule is tight but ... we can work hard to fulfill it.
- *" No evidence that ATLAS chambers will have problems if operated according to design conditions "*  
LHCC referee conclusion