

# Status of trigger chamber production

# ATLAS LHCC Comprehensive Review July 2-3, 2001

S. Patricelli
University of Naples and INFN







### **Outline**

### Barrel trigger chambers (RPC)

- RPC description
- Organization of production
- Production status
- Front-end electronic production status

# End-Cap trigger chambers (TGC)

- Chamber production status
- Quality Control of chambers with Cosmic Rays
- Front-end electronic production status



### **RPC** Basic Unit



To cover 3.500 m<sup>2</sup>:

1004 Standard Units

16 different dimensions97% coverage

132 Special Units (with holes for alignment bars)

4 different dimensions3% coverage




### One Unit is a double sandwich

#### Gas volumes

### Cu readout electrode panels






Paper honeycomb and Al support panels (Faraday cage)
Al lateral profiles



### Front-End electronic is inside

Front-End boards with 8ch GaAs \_ 3 stage amplifier and discriminator





Back-End boards with terminating resistors and test pulse distribution



### Production principles

Bakelite plates: 7.360

Gas volumes: 3.680

| Electrode readout panels: 8.560


IF.E. and B.E. Boards: 48.148

Readout channels: 385.184

- All parts are produced by industry.
- To avoid duplication of tools and have higher efficiency in production, all additional works on detector parts are done in only one site.




### Production flow chart






# Readout panels preparation



(Rome 2)



Precison holes punching (Naples)



Front-End board mounting (Rome 2)



# Unit assembly in Lecce



Services mounted



Applying pressure with pneumatic tool



On transport and storage fixture



# RPC Quality Assurance

# Three test stations are operational Tracking of CR is done with RPCs or Drift Chambers



Lecce

Roma2





**Naples** 

Each station allows the simultaneous test of 8 Units



### Pre-production

- A set of three BMS Units was assembled last year as a first test of assembly.
- Front-End and Back-End boards for these Units are not the final ones.
- Main goals of this preproduction were:
  - I define all tools necessary for the assembly phase.
  - I finalize services for the Units.



# Start of production (1)

- Due to delay of tender procedures for Front-End boards production (inside the detectors!) the decision was taken to start production with a special order for 1.500 boards.
- The delivery of these boards had 2 months delay.
- These boards have allowed the (almost completed) production of 24 Units, 16 for BOS and 8 for BOL chambers (largest size).




# Start of production (2)

- All assembly tools and procedures for assembly of Units are now done or understood.
- Production database (MS Access) is operational.
- Unit assembly rate: 3 Units/day. Not a bottleneck.
- A new assembly hall (no delay in production) is being prepared in Lecce.



### **RPC Production Schedule**





# Mass production

Bakelite plates: on schedule

Electrode readout panels: on schedule

GaAs Front-End chips: produced (50.000)

Support panels: on schedule

Al profiles: produced and machined

Gas volumes: 2-3 months stand-by to

implement higher Q.C.

(next talk)

Front-End Boards: 4-5 months delay (from

industry)



### Front-end boards status



- GaAs chip with 8 channels 3 stage amplifier & comparator (GIGA).
- All 50k chips produced
- 1st DC test done by DELTA
- PC boards are of 3 different dimensions produced by Zener (Italy)
- Chip bonding 2<sup>nd</sup> DC test done by industry in Microtel (Italy)
- Delivery at Roma 2



### Front-end boards test




- AC test devoted to check the dynamic functionality of all channels and used to build the database
- In future also thermal cycle
- Disagnostic Set Up to used to find recurring defects caused by wafer and chip handling
  - Yield on present production
    - **I** 1102/1400 = 78.8 %






### Front-end boards test results


#### 'Response Dispersion' and the corresponding Amplification Factor



# Power Consumption per channel



# No significant Temperature dependence





### **RPC Summary**

- Production tools are ready.
- Production procedures are understood.
- Q.C. during gas volume production is being improved.
- Cosmic ray test stations operational.
- Mass production has started.
- Front-end PC boards are of good quality but have 4-5 months delay which will influence Units assembly.
- Schedule is tight but still possible to finish by 2003.